



## Stieglitz Snyder Architecture

425 Franklin Street  
Buffalo, New York 14202  
Tel – 716.828.9166 Fax – 716.828.9164  
www.stieglitzsnyder.com

September 20, 2019

### **ATTENTION: ALL BIDDERS**

Re: **Interior Renovations Project at:  
Bissonette House  
335 Grider Street, Buffalo, NY 14215**

### **PRE-BID ADDENDUM No. 2:**

Prime contract bidders of record for the subject project are hereby informed that this Addendum forms a part of the Contract Documents and modifies the original drawings and specifications issued as noted below. Receipt of the Addendum shall be acknowledged on the bid form.

### **GENERAL:**

#### **ITEM: 1**

*Information:*

**ATTENTION: BID DATE EXTENSION  
BID DUE DATE: OCTOBER 1, 2019 AT 11:00 A.M.**

#### **ITEM: 2**

*Information:* Hazardous Materials Test Report is forthcoming and to be issued as Addendum.

### **DRAWINGS AND SPECIFICATIONS:**

#### **ITEM 3:**

*Refer to:* Contract Drawings, A101 Door Replacement Plans, Schedules And Notes

*Add:* **ALTERNATE #4: New wood doors at these four (4) locations:**  
*Door #201 (at Hallway 201) 31-1/2" x 80".*  
*Door 300A (at Closet 300A) 24" x 78".*  
*Door 300B (at CL. 300B) 29-1/2" x 79".*  
*Door 306A (at CL. 306A) 23" x 78".*

*These are all closet doors and are to receive Hardware Set #03.*

**ITEM 4:**

*Refer to:* Contract Drawings, A103 Basement Ceiling Plan And Miscellaneous and Bidders Checklist package, sheet P-1, page 3 of 48,

*Clarification:* *Alt #3 New basement SACT replacement.*

*This is a separate dollar value for replacing the basement SACT (Suspended Acoustic Ceiling Tile) system and Ceiling Troffer Fixtures.*

**ITEM 5 :**

*Refer to:* Contract Drawings, A101 Door Replacement Plans, Schedules And Notes

*Clarification:* *Door Schedule First Floor*

*Door #104A Hdwr. Type 4 to be changed to Hdwr. Type #03.*

**ITEM 6 :**

*Refer to:* Contract Specifications, Flush Wood Doors, 081416-3, 2.4, A, 2. Species.

*Clarification:* *Species to be Douglas Fir.*

**ITEM 7 :**

*Refer to:* Contract Drawings, A101 Door Replacement Plans, Schedules And Notes

*Add:* **DEMOLITION & CONSTRUCTION NOTES:**

6. *At locations of all hardware removals from framed openings including but not limited to hinges, closers, strikes, barrel bolts, hasps and all other associated hardware infill and patch all holes or voids in wood frame to match flush with adjacent surfaces to conceal evidence of that hardware removal. Paint all infill and patched locations to match color and paint sheen of wood frame casings.*

**ITEM 8 :**

*Refer to:* Contract Drawings, A100 Floor Finish Plans and Notes (At Flooring Carpet).

*Add:* **DEMOLITION & CONSTRUCTION NOTES:**

6. *All perimeter toe kick or wall base materials damaged or broken during removal are to be replaced with new materials to match in kind and finished to match existing. All to kick and wall base material nail holes in new and existing are to be patched and infilled. Paint all patched and infilled locations to match color and paint sheen of existing wood toe kick or wall base.*